SANITARY.

PROCEEDINGS OF THE CENTRAL SANITARY BOARD IN MYSORE.

READ—

Letter No. B. 7470, dated the 10th June 1919, from the Chief Engineer of Mysore, forwarding an estimate amounting to Rs. 11,000 for laying out extensions to Koppa town in three directions to save the requirements of the different parts of the town.

Resolution No 12, *dated* 23*rd August* 1919.

Resolved (1) that as the population of Koppa town is only 700, the prospective being taken as 1,000, only one extension providing for 40 houses and 21 cottages may, for the present, be laid out at the upper or south-western part of the town and (2) that the site, about 19 acres in extent, proposed, be approved.

READ—

Letter No. C. 553, L. F. dated the 15—16th May 1919, from the Deputy Commissioner, forwarding an estimate amounting to Rs. 6,030 for the improvement of drainage in the Nelamangala town, the items of work being (1) the construction of two intercepting drains designed to discharge all the sullage and 1/16th inch of rainfall and (2) provision of an underground stoneware sewer to lead the sullage from where the intercepting drains meet, on to a cistern wherefrom it is taken for treatment on land.

Resolution No. 13, *dated the* 23*rd August* 1919.

Resolved (1) that the estimate be approved and (2) that, in view of the low state of finances of the Municipal Council, Government be moved to sanction a grant-in-aid equivalent to three-fourths of the cost of the scheme, out of State Funds.

T. V. ARUMUGAM,
President.